



Jalore Nagrik Sahakari Bank Ltd.

Head Office : Rajendra Nagar Road, Jalore (Rajasthan)

Email ID :- headoffice@jalore.bank.in | Bank Website :- www.jalore.bank.in | Mobile No. 90798-06434

TENDER DOCUMENT

FOR

BRANCH- AHORE

(Dist. – Jalore)

**FURNITURE,
ELECTRIC FITTING,
CEILING & INTERIOR
WORK**


Jalore Nagrik Sahakari Bank Ltd.

Head Office : Rajendra Nagar Road, Jalore (Rajasthan)

Email ID :- headoffice@jalore.bank.in | Bank Website :- www.jalore.bank.in | Mobile No. 90798-06434

CONTENTS

क्र. संख्या	विवरण	पृष्ठ संख्या
01	निविदा सूचना	03
02	सामान्य नियम एवं शर्तें	04-07
03	फर्नीचर निर्माण, इलेक्ट्रीक फिटिंग, सिलिंग एवं इन्टीरियर कार्य की अनुसूची	08-13
04	घोषणा	14





Jalore Nagrik Sahakari Bank Ltd.

Head Office : Rajendra Nagar Road, Jalore (Rajasthan)
Email ID :- headoffice@jalore.bank.in | Bank Website :- www.jalore.bank.in | Mobile No. 90798-06434

क्रमांक / जानासबैकलि / ५१२९

दिनांक 23.07.2026

निविदा सूचना

जालोर नागरिक सहकारी बैंक लिमिटेड बैंक को अपनी शाखा आहोर (जिला-जालोर) के नवीन भवन हेतु निश्चित डिजाइन अनुसार फर्नीचर, इलेक्ट्रीक फिटिंग, सिलिंग एवं इन्टीरियर डिजाईनिंग का कार्य अतिशीघ्र करवाया जाना प्रस्तावित हैं। (उक्त कार्य में बैंक की जालोर शाखा के काउन्टर एवं वर्तमान आहोर शाखा का फर्नीचर आवश्यकतानुसार उपयोग में लिया जाना है।) इस हेतु पंजीकृत एवं प्रतिष्ठित फर्मों/कम्पनियों (GST Firm) से निविदा प्रस्ताव आमंत्रित किये जाते हैं।

अतः इच्छुक पंजीकृत एवं अनुभवी, प्रतिष्ठित फर्म / कम्पनी (GST Firm) अपनी निविदा (Technical & Financial Bid) के अलग-अलग सील बन्द लिफाफे में दिनांक 07.08.2026 को दोपहर 2 बजे तक बैंक प्रधान कार्यालय स्थित मुख्यकार्यकारी अधिकारी के कक्ष में रखे गये टेण्डर बॉक्स में डालना सुनिश्चित करें। निविदायें दिनांक 07.08.2026 को सांय 4 बजे खोली जाएगी। Layout एवं Detailed Plan बैंक के प्रधान कार्यालय में उपलब्ध हैं, जो निविदा शुल्क जमा करवाने पर प्राप्त कर सकते हैं।

बैंक की अधिकृत कमेटी आवश्यकताओं के दृष्टिगत विभिन्न पहलुओं के आंकलन के आधार पर निविदा को अस्वीकृत/अंतिम रूप से स्वीकृत करने हेतु अधिकृत होगी, जो सभी पक्षों के लिए अंतिम रूप से बाध्यकारी होगा।

विस्तृत विवरण, शर्तें, मात्रा इत्यादि की सम्पूर्ण जानकारी बैंक की वेब साईट www.jalore.bank.in पर उपलब्ध है।

आज्ञा से
(परमानन्द भट्ट)
मुख्य कार्यकारी अधिकारी
जालोर नागरिक सहकारी बैंक लि.



Jalore Nagrik Sahakari Bank Ltd.

Head Office : Rajendra Nagar Road, Jalore (Rajasthan)

Email ID :- headoffice@jalore.bank.in | Bank Website :- www.jalore.bank.in | Mobile No. 90798-06434

01	सामान्य नियम एवं शर्तें		
1.0	सामान्य जानकारी	—	फर्नीचर निर्माण, इलेक्ट्रीक फिटिंग, सिलिंग एवं इन्टीरियर कार्य हेतु
1.1	कार्य का नाम	—	फर्नीचर निर्माण, इलेक्ट्रीक फिटिंग, सिलिंग एवं इन्टीरियर कार्य
1.2	फर्नीचर निर्माण, इलेक्ट्रीक फिटिंग, सिलिंग एवं इन्टीरियर कार्य करने का पत्ता	—	जालोर नागरिक सहकारी बैंक लि., मैन बाजार, आहोर जिला—जालोर (राजस्थान)
1.3	निर्माण/आपूर्ति की अवधि	—	कार्य कार्यादेश जारी होने की तिथी से तीन माह के भीतर पूर्ण करना होगा।
02	रेट टेण्डर/निविदा पत्रों के साथ प्रस्तुत दस्तावेज		
	तकनीकी (Technical) एवं वित्तीय (Financial) Bid अलग-अलग लिफाफे में प्रस्तुत करनी होगी।		
2.1	तकनीकी (Technical) Bid में निविदादाता निम्नलिखित दस्तावेज प्रस्तुत करेगा—		
a)	फर्म रजिस्ट्रेशन की प्रति प्रस्तुत करनी होगी।		
b)	नवीनतम आयकर रिटर्न प्रस्तुत करना होगा।		
c)	जीएसटी नम्बर की प्रतिलिपी प्रस्तुत करनी होगी।		
d)	वित्तीय वर्ष 2024-25 का Turn Over प्रस्तुत करना होगा।		
e)	रेट टेण्डर/निविदा शुल्क एवं अमानत राशि का विवरण प्रस्तुत करना होगा।		
f)	ई-ट्रांसफर भुगतान हेतु सूचना प्रस्तुत करनी होगी— 1. फर्म का नाम मय पत्ता 2. बैंक का नाम मय पत्ता 3. खाता संख्या एवं खाते का प्रकार 4. IFSC Code नं. 5. पेनकार्ड की प्रति। 6. जी.एस.टी.नं. 7. सुलभ संदर्भ हेतु एक केन्सिल चैक		
g)	तकनीकी (Technical) Bid में निविदादाता को इसी प्रकार के पूर्व में किये गये कार्यों के कार्यादेश, कार्य पूर्णता प्रमाण पत्र, इंजीनियर की संख्या, प्रोजेक्ट हैड की संख्या, सुपरवाइजर की संख्या, लेबर की संख्या, टूल्स/मशीनरी, कार्य का विस्तृत विवरण जिसमें स्थान, कार्य पूर्ण करने की दिनांक सहित कार्यस्थल के फोटो संलग्न करने होंगे ताकि तकनीकी रूप से अनुभव व कार्य का मुल्यांकन किया जा सके।		
2.2	वित्तीय (Financial) Bid में निविदादाता निम्नलिखित दस्तावेज प्रस्तुत करेगा—		
a)	वित्तीय (Financial) Bid में कार्य की दर(जीएसटी कर सहित / कर रहित) प्रस्तुत करनी होगी एवं दरें गन्तव्य स्थान तक FOR के संबंध में पूर्ण जानकारी देनी होगी। रेट टेण्डरदाता द्वारा मूल रेट टेण्डर दस्तावेज पर जहां भी आवश्यक हो उसमें दर भर कर प्रत्येक पेज में सील और हस्ताक्षर के साथ सील बंद लिफाफे में प्रस्तुत करना होगा।		

निविदादाता फर्म के हस्ताक्षर मय सील

b)	निविदा प्रारूप स्याही से भरा जाएगा या टंकण से भरा जाएगा। पैसिल से भरी गयी किसी भी निविदा पर विचार नहीं किया जाएगा। निविदादाता निविदा के प्रत्येक पृष्ठ पर हस्ताक्षर करेगा तथा अन्त में निविदा की समस्त शर्तों को स्वीकार करने के प्रमाण में हस्ताक्षर करेगा।
c)	आईटम वार दर स्पष्ट लिखे तथा कुल योग की दरें शब्दों एवं अंकों दोनों में लिखी जाएगी। इसमें कोई त्रुटियां (Errors) एवं/या उपरिलेखन नहीं होना चाहिए। यदि कोई शुद्धियां करनी हो तो स्पष्ट रूप से की जानी चाहिए एवं दिनांक सहित उन पर लघुहस्ताक्षर किए जाने चाहिए। दरों में राजस्थान बिक्री कर एवं केन्द्रीय बिक्री करों की राशि को पृथक से दिखाना चाहिए।
2.3)	तकनीकी (Technical) Bid में सफल होने वाले निविदादाताओं की वित्तीय (Financial Bid) खोली जाएगी।
03	टेण्डर/निविदा शुल्क, अमानत राशि एवं सुरक्षा जमा राशि :-
3.1	निविदा शुल्क – राशि 2.50 लाख से उपर की खुली निविदा (Open Tender) होने पर निविदा/टेण्डर शुल्क कुल अनुमानित राशि का 0.05 प्रतिशत या न्यूनतम रु. 500/- जमा करवाना होगा जो Non Refundable होगा। (राशि 2,50,000/- रु. तक की खरीद सर्विस/कार्य हेतु टेण्डर फीस की आवश्यकता नहीं रहेगी)
3.2	अमानत राशि (Earnest Money) – राशि 2.50 लाख से उपर की खुली निविदा (Open Tender) होने पर अमानत राशि निविदा लागत का 2.00 प्रतिशत जरिये ड्राफ्ट/IMPS, RTGS & NEFT द्वारा जमा करवाना होगा। निविदा जमा करवाते समय एक लिफाफे में निविदा एवं एक लिफाफे में अमानत राशि का ड्राफ्ट अथवा ऑनलाईन जमा करवायी गयी राशि की UTR विवरण स्लीप डालकर बैंक में प्रस्तुत करना होगा। निविदा खोलने से पूर्व अमानत राशि बैंक में जरिये ड्राफ्ट/IMPS, RTGS & NEFT द्वारा प्राप्त होनी आवश्यक हैं। जो निविदा अस्वीकृत होने पर पुनः लौटायी जाएगी। (राशि 2,50,000/- रु. तक की खरीद सर्विस/कार्य हेतु अमानत राशि की आवश्यकता नहीं रहेगी)
	सुरक्षा जमा राशि (Security Deposit) – राशि 2.50 लाख से उपर की खुली निविदा (Open Tender) होने पर निविदा स्वीकृत होने पर सुरक्षा जमा राशि निविदा अनुसार आदेश की लागत का 5 प्रतिशत प्राप्त की जाएगी। जिसमें अमानत राशि 2 प्रतिशत का समायोजन किया जाएगा। जिस पर कोई ब्याज देय नहीं होगा। उक्त राशि निविदा का अंतिम निर्णय लेने के अगले दो दिवस में जरिये ड्राफ्ट / IMPS, RTGS & NEFT द्वारा बैंक में जमा करवानी होगी अन्यथा निविदा L-2 के पक्ष में स्वीकृत कर दी जाएगी। सुरक्षा राशि जमा नहीं करने पर L-2 के पक्ष में निविदा Final की जाएगी। उक्त राशि जमा होने के पश्चात सम्बन्धित फर्म के पक्ष में आदेश जारी किया जाएगा। सुरक्षा जमा राशि निविदा आदेश के अनुसार सामग्री/सेवा प्राप्ति की पूर्ण संतुष्टि के पश्चात् लौटायी जायेगी। (राशि 2,50,000/- रु. तक की खरीद सर्विस/कार्य हेतु सुरक्षा राशि की आवश्यकता नहीं रहेगी)
3.3	रेट टेण्डर/निविदा दाता द्वारा टेण्डर शुल्क एवं अमानत राशि जमा नहीं करवाने पर प्रस्तुत रेट टेण्डर/निविदा पर विचार नहीं किया जायेगा एवं निविदा अस्वीकार कर दी जाएगी।

3.4	रेट टेण्डर/निविदादाता द्वारा प्रस्तुत टेण्डर/निविदा शुल्क, अमानत राशि एवं सुरक्षा जमा राशि के विरुद्ध बैंक द्वारा कोई ब्याज नहीं दिया जाएगा।
3.5	रेट टेण्डर/निविदा स्वीकृत करने के उपरान्त फर्म द्वारा यदि फर्नीचर निर्माण, इलेक्ट्रीक फिटिंग, सिलिंग एवं इन्टीरियर कार्य में असमर्थता, कम गुणवत्ता या आदेशानुसार प्राप्त नहीं होने पर अमानत राशि जब्त की जाएगी।
04	रेट टेण्डर/निविदा दाता द्वारा मूल रेट टेण्डर/निविदा दस्तावेज को प्रत्येक पृष्ठ पर हस्ताक्षर मय सील सहित प्रस्तुत करना होगा।
4.1	रेट टेण्डर/निविदा दाता द्वारा रेट टेण्डर/निविदा व्यक्तिगत रूप से जमा करवाई जा सकती है या पोस्ट(डाक) द्वारा भेजा जा सकता है ताकि रेट टेण्डर/निविदा सूचना में उल्लेखित समय के भीतर पहुंचने के लिए आवेदन किया जा सके।
4.2	रेट टेण्डर/निविदा दाता द्वारा प्रस्तुत की गयी दर रेट टेण्डर/निविदा खोलने की दिनांक से 1 वर्ष तक के लिए मान्य रहेगी और संवेदक को उसी अनुमोदित दरों पर आदेशानुसार आपूर्ति करनी बाध्यकारी होगी।
4.3	रेट टेण्डर/निविदा को सीलबन्द कर प्रधान कार्यालय स्थित टेण्डर बॉक्स में निम्नांकित पते पर जमा करवाने होंगे – मुख्य कार्यकारी अधिकारी, जालोर नागरिक सहकारी बैंक लि., प्रधान कार्यालय –राजेन्द्र नगर रोड़, जालोर– 343 001 (राजस्थान)
4.4	रेट टेण्डर दर में जी.एस.टी दर सम्मिलित है अथवा नहीं जी.एस.टी. को अलग से दर्शाया जाये।
05	रेट टेण्डर/निविदा विलम्ब के कारण देय तिथि/ समय के बाद बैंक को प्राप्त होने पर रेट टेण्डर/निविदा को अस्वीकार कर दिया जायेगा।
06	बैंक द्वारा रेट टेण्डर/निविदाओं को खोलना :-
6.1	बैंक द्वारा प्राप्त रेट टेण्डर/निविदाओं को बैंक की अधिकृत कमेटी/संचालक मंडल बैठक के समक्ष खोला जायेगा।
6.2	रेट टेण्डर/निविदाओं को खोलने के पश्चात प्राप्त रेट टेण्डर/निविदाओं की दरों को तुलनात्मक विवरण बना कर प्राप्त सबसे कम दर वाली फर्म को आवश्यकतानुसार आदेश दिया जायेगा।
07	मात्रा :-
7.1	बैंक द्वारा सूची में उल्लेखित मात्रा केवल अनुमानित मात्राएं हैं जो रेट टेण्डर/निविदा दाता द्वारा आपूर्ति की जाने वाली वास्तविक और सटीक मात्रा के रूप में नहीं ली जा सकती है। बैंक आवश्यकतानुसार फर्नीचर निर्माण, इलेक्ट्रीक फिटिंग, सिलिंग एवं इन्टीरियर कार्य हेतु मात्रा और गुणवत्ता या इसके किसी भी हिस्से में परिवर्तन कर सकता है।

निविदादाता फर्म के हस्ताक्षर मय सील

7.2	सूची में वर्णित मात्रा की वृद्धि या कमी करने का अधिकार बैंक के पास सुरक्षित रहेगा।
7.3	बैंक द्वारा लिखित किसी आदेश के बिना रेट टेण्डर/निविदा दाता द्वारा कोई बदलाव नहीं किया जायेगा।
08	खरीद आदेश जारी करना :-
8.1	रेट टेण्डर/निविदादाता फर्नीचर निर्माण, इलेक्ट्रीक फिटिंग, सिलिंग एवं इन्टीरियर कार्य आदेश की प्राप्ति के तीन माह की अवधि के भीतर पूर्ण करेगा। फर्नीचर, इलेक्ट्रीक फिटिंग, सिलिंग एवं इन्टीरियर कार्य हेतु Layout & Detailed Plan बैंक द्वारा प्रदान किया जावेगा एवं कार्यादेशानुसार कार्य करना होगा, जिसमें Transportation का Charges देय नहीं होगा।
09	निरस्त करना :-
9.1	रेट टेण्डर/निविदा दाता द्वारा निर्धारित समयावधि के भीतर फर्नीचर निर्माण, इलेक्ट्रीक फिटिंग, सिलिंग एवं इन्टीरियर कार्य समय पर पूर्ण नहीं करने पर आदेश निरस्त कर सुरक्षा राशि जब्त की जा सकती है। इसके साथ ही संवेदक की Risk & Cost पर अन्य से माल खरीदी की जा सकेगी जिसकी समस्त व्यय संवेदक से वसूल किया जाएगा।
10	भुगतान :-
10.1	रेट टेण्डर/निविदादाता द्वारा दिये गये फर्नीचर निर्माण, इलेक्ट्रीक फिटिंग, सिलिंग एवं इन्टीरियर कार्य आदेश के अनुसार आपूर्ति/निर्माण के पश्चात बिल बैंक में प्रस्तुत करना होगा। आपूर्ति की गयी सामग्री के सत्यापन कार्य की गुणवत्ता, नाप की जांच एवं बैंक के अधिकृत वास्तुकार /वेल्युअर द्वारा जारी उपयोगिता प्रमाण पत्र प्रस्तुत करने के पश्चात भुगतान किया जाएगा।
11	दंड :-
11.1	रेट टेण्डर/निविदादाता द्वारा फर्नीचर निर्माण, इलेक्ट्रीक फिटिंग, सिलिंग एवं इन्टीरियर कार्य के निर्माण कार्य एवं आपूर्ति से इन्कार करता है या सप्लाई करने में विफल रहता है तो बैंक सुरक्षा जमा राशि भी जब्त कर सकता है। जिसकी जिम्मेदारी संवेदक की रहेगी।
12	विविध :-
	बैंक किसी भी या सभी रेट टेण्डर/निविदाओं को बिना किसी कारण बताए रद्द करने का अधिकार सुरक्षित रखता है। किसी भी उपर्युक्त कारणों से रेट टेण्डर/निविदादाता के द्वारा शर्तों के उल्लंघन दर्ज होना पाये जाने पर बैंक उसके साथ किए गए करार को समाप्त कर शेष बचे रेट टेण्डर/निविदादाताओं में से किसी भी एक के साथ नियमानुसार आदेश देने की प्रक्रिया प्रारम्भ करने का अधिकार रखता है।
13	अंतिम निर्णय :-
	किसी भी परिस्थिति में टेण्डर संबंधी अंतिम निर्णय बैंक की संबंधित कमेटी का ही मान्य एवं सभी पक्षों के लिए बाध्यकारी होगा।

निविदादाता फर्म के हस्ताक्षर मय सील

**The BOQ & Material description of Furniture, Electric Fitting, Ceiling
& Interior work for the
Jalore Nagrik bank Ltd., Branch Ahore**

Furniture/Ceiling work.					
Sr No	Item	Description (with Location merged)	Qty	Size	
A.1.1	Table	Cash Counter 07 – Repair existing table, replace laminates, add under-table storage (300×450×630 mm).	1	1300×600×750 mm	
A.1.2	Table	Counters 01–06 – Repair existing tables, replace laminates, add under-table storage.	6	1300×600×750 mm	
A.1.3	Officer Desk	Branch Manager Office – Front table (1350×750×750 mm) with glass top; side table (450×900 mm) with drawers.	2	1350×750×750 mm	
A.1.4	Table Glass	Counter 05 – 10 mm glass on table top.	1	1300×600×750 mm	
A.1.5	Table Glass	Branch Manager Office – 10 mm glass on desk top.	2	1500×600×750 mm	
A.2.1	Mirror + Table	Locker – Dressing mirror (450×900 mm) + table (450×300 mm).	1	450×300 mm	
A.2.2	Mirror	Washroom – Dressing mirror (450×900 mm).	1	450×900 mm	
A.3.1	Partition Wall	Counter 06 – Solid + frosted glass partition with aluminium frame.	1	3562×1800 mm	
A.3.2	Glass Partition	Counter 06 – Front frosted glass partition.	2	1400×600 mm	
A.3.3	Glass Partition	Counters 01–05 – Front frosted glass partition.	5	1300×450 mm	
A.4.1	Upper Cabinets	Branch Loan Office – 11 cabinets installed at 1350 mm height.	11	1000×1350×450 mm each	
A.4.2	UPS Cabinet	Ground Floor – Ventilated cabinet with granite top.	1	1500×1350×700 mm	
A.4.3	Upper Cabinet	Ground Floor (Above UPS) – Single cabinet installed at 1350 mm height.	1	1500×1350×450 mm	
A.4.4	Full Height Cabinet	Site Condition – Relocated/refurbished cabinet.	1	1800×3700×450 mm	
A.5.0	Glass Partition	Branch Manager Office – Frosted glass partition with door.	1	2100×6000 mm	
A.5.2	Glass Door	Branch Manager Office – Clear glass door with aluminium frame.	1	750×2100 mm	
A.6.0	Glass Partition	Main Gate – Glass partition with door.	1	2850×2500 mm	
A.6.2	Glass Door	Main Gate – Clear toughened glass door with hardware.	1	750×2100 mm	

A.7.0	Glass Partition	ATM Room – Aluminium framed glass partition with door.	1	2100×1650 mm	
A.8.1	ACP Work	ATM/CDS – ACP cladding with aluminium base.	1	10 sq. m	
A.9.1	Water Purifier	Ground Floor – RO+UV+UF system, 20–25 LPH, 10–12 L tank.	1	Unit	
A.9.2	Sink with Tap	Washroom Outer Wall – Sink (375×450 mm), CP mixer, valves.	1	Unit	
A.10.1	Ceiling	Ground Floor – Ceiling tiles (600×600 mm), GI grid framework.	1	125 sq. m	
A.11.1	Name Board + Cladding	Outdoor Bank Front – ACP cladding with acrylic letters.	1	4.5×2.25 m	
A.11.2	Acrylic Letters	Outdoor Bank Front – Illuminated acrylic signage (Bank name + ATM).	1	300 mm height	
A.12.1	Benches	Waiting Area – Metal benches with cushioned tops.	2	2 m length	

Electrical work.

Sr No	Item	Description (Location merged)	Qty	Size/Rating	
E.1.1	AC	Ground Floor – 3 Ton, 4-Way Cassette AC (Voltas CAS-36CZAA or equivalent), complete installation.	3 units	3 Ton each	
E.2.1	Copper Piping	Ground Floor – For 3 Ton Cassette ACs, copper suction/liquid lines, drain pipe, cabling.	3	20 m each (60 m total)	
E.2.2	Copper Piping	Basement – For 1.5 Ton Split AC.	1	25 m	
E.2.3	Copper Piping	Basement – For 1 Ton Split AC.	1	5 m	
E.3.1–E.3.8	MCBs	Distribution – Single/Double/Four pole MCBs, ratings 0.5–40 A, ISI marked.	8	As specified	
E.4.1	MCCB	Main Incomer – MCCB 50/63 A rating.	1	63 A	
E.5.1	RCCB	Distribution – RCCB 63 A, 30 mA, 2/4 pole.	1	63 A	
E.6.2	DB	Distribution – Double door TPN DB, 8 Way (8+24), IK-09 & IP-43.	2	100 A copper bus bar	
E.7.1	Switch	Banking Area – 6–10 A one-way modular switches.	64	6–10 A	
E.7.2	Switch	Banking Area – 16 A one-way switch with LED indicator.	8	16 A	
E.7.3	Switch	Banking Area – 32 A one-way switch with LED indicator.	4	32 A	
E.8.2	Socket	Banking Area – 6/16 A shuttered sockets.	64	6/16 A	
E.8.3	Socket	Banking Area – 32 A, 2-module sockets.	4	32 A	
E.9.1	Data Cabling	Ground Floor/ATM – CAT-6 UTP cables (~20 m each).	14	20 m each	
E.9.2	Telephone Jack	Ground Floor/ATM – RJ-11 single line.	2	Unit	
E.9.5	Computer Jack	Ground Floor/ATM – RJ-45 Cat-6 I/O box with shutter.	14	Unit	
E.10.2	Module Plate	Banking Area – 3-module plates.	9	Unit	

Handwritten signature

E.10.5	Module Plate	Banking Area – 8-module plates.	17	Unit	
E.10.6	Module Plate	Banking Area – 12-module plates.	2	Unit	
E.10.7	Module Plate	Banking Area – Blanking plates.	2	Unit	
E.11.1	Fan	Banking Area – Wall-mounted fans (Bajaj or equivalent).	7	Unit	
E.12.1	CCTV	Bank Area – CCTV cameras (Hikvision/CP Plus/Dahua).	6	Unit	
E.12.2	CCTV Cabling	Bank Area – CAT-6 cable RJ-45 (~20 m each).	6	20 m each	
E.13.3	Wiring	Bank – Long point wiring (up to 10 m).	12	2.5 sq mm copper	
E.14.3	Wiring	Bank – Long point earth conductor wiring (UPS).	1	4 sq mm copper	
E.15.0	Cable Track	Bank – 300 mm perforated cable track with cover.	15 m	300 mm wide	
E.16.1	Lights	Banking Area – 40 W recessed LED panel lights (600×600 mm).	15	40 W	
E.16.2	Lights	Banking Area – 18 W recessed LED panel lights.	25	18 W	
E.17.1	Conduit	Bank – PVC conduit (25 mm or site condition).	200 m	25 mm	
E.18.1	Exhaust System	Banking Area – Ceiling-mounted ventilation units.	3	Unit	
E.18.2	Exhaust Duct	Banking Area – 200 mm PVC duct.	20 m	200 mm	
E.18.3	Exhaust Duct	Banking Area – 250 mm PVC duct.	20 m	250 mm	
E.18.4	Inline Fan	Banking Area – 10-inch inline duct fans, copper motor.	3	250 mm	
E.19.1	DB Panel	Banking Area – Main electrical DB panel, complete with MCBs/RCCBs.	1	Unit	

Notes:

1	Read the document along with the respective layout drawings. If any basic details of the listed assets are missing, the bidder must account for them while preparing the tender.
2	For any queries, please refer to the drawings, working notes, reference images, or contact the bank directly.
3	Design, details, and item quantities may vary by approximately 10%. Please consider this variation while bidding.
5	BOQ quantity variation (+/-) will be finalized based on actual site execution.
6	Detailed drawings will be provided for furniture and joinery works.
7	Technical specifications for CCTV and security systems will be provided by the client.
8	In case of any discrepancy between the BOQ description and the bidder's interpretation, record the details in the Remarks column while filling out the tender.
9	Painting is not included in the scope of work, as it has already been completed on site. However, during execution, if any visible marks or damage occur on walls or painted areas, the contractor shall be responsible for rectifying and repainting those portions to match the existing finish. This rectification is mandatory to ensure the final handover maintains the required quality standards.
10	The total estimated cost for the scope of works described in the BOQ is ₹ 12,00,000/-.

Material description:

Sr. No	Item	Description
1	Table	
	Plywood	18mm or as described. MR grade. IS 303: Brand must be genuan and non comertial, for 18 mm ply wood range must be 100 to 125 rupees per sq.ft. and equivalent for other thinkess of the plywood and black board as per requirement.
	Laminate:	Laminate for high traffic area as it should be high pressure laminates. Top laminate Range : up to 2000 per sheet. Brand : Green-ply or equivalent.
	Drawer channel and locks	Channel = Enox/hattich
		Lock = Hafle/Dorset,
		Handle = Deccowell
	Fixing	Fevicol, SS screw or SS nails.
	Electrical point	Brand: GM
		Staff: 4 plug sockets with switch, Ethernet cable point.
		Officer: 5 plug sockets with switches, Ethernet cable point, Intercom connection point.
		under table.
2	Partition Wall Solid	
	AL. section	50 mm X 50 mm box section or as described in details, gauge 16.
	Plywood	12mm at each side. MR grade.
	Laminate:	High pressure laminates, crack and heat up to 180-degree dry heat resistant and till 4.
3	Glass Partition	
	Glass	12mm glass, frosted or fluted.
	Section	Slim section (50 mm X 25 mm or slim), gauge 16. or per selection.
	Plywood	MR grade, IS:303
	AL section	25 mm gauge 16.
	Door Fittings	Hafle/ Enox/hattich
4	Electrical:	
	Wire	RR, Ploycab or equivalent.
	Switches:	GM, L&T or equivalent.
	CAT-6 cable	D-Link or equivalent.
	Lights:	Minimum 2 years of warranty and service.
	Fan	Brand: Crompton, Bajaj or equivalent.
		High speed, Minimum 2 years of warranty.
	Cable pipe	Pvc pipe, Viraj or Pision brand.
	MCB, RCCB. etc	GM, L&T or equivalent.
5	AC	Voltas Company
	AC pipe & wire.	Copper pipe & 4 sq. m.m. wire.
6	Plywood (for whole work)	MR grade. IS 303: Brand must be genuan and non comertial, for 18 mm ply wood range must be 100 to 125 rupees per sq.ft. and equivalent for other thinkess of the

6211

		plywood and black board as per requirement.
7	Paint	Asian paint.
8	ceiling	Indian gypsum, Armstrong, Saint-Gobain Gyproc, and Knauf or equivalent. Section: Aesco, BOSCH, USG Boral, Royal Kraft or similar Ceiling Channel.
9	Door:	30 mm flush door both side 1mm laminate finish , brass hinges , SS locks and AL stopper
10	Chairs	Hight adjustable chair, rotating mechanism with 5 Castro Wheel. Based material: Nylon Seat: PU foam Lift: minimum Class 4

Notes and work description.

1	Please follow the notes from the layout and detailed drawing.
2	All the laminates, plywood, wire, cables, glass, etc. must be single-unit work, as there should be no joint until and unless it's described in the drawing.
3	Electrical notes:
a	The wire brand is Polycab.
b	Use 3 gauges of wires, 1.5mm, 2.5 mm, and 4mm wires, for the power supply within the building.
c	For earthing connection, use 1mm of wire.
d	Use a single connection for each switchboard club to the MCB point circuit. The wire between the power is 2.5 mm.
e	There should be no looping (neutral wire looping) in any condition. Run two wires (power and neutral wires) for each switch connection. Use 1.5mm wire for lights, fans, or any other equipment that consumes less energy.
f	Use the track system to move the wires once it has become more than 3 wires conducting in pipes. Please follow the CAD file to get the track location and path.
g	There should be no joint
h	For AC, use 4mm wire
I	For a 3-ton AC unit, a Type C MCB with a rating of 32 amps.
J	The power connection to the wire: please keep 2m of extended wire.
K	Provide the UPS connection to tables (to power computers and printers), bank server, a few strategic lights, and fans.
l	The branch server will be located at the northeast corner of the branch manager's office, and the power switch will be near the branch manager's table. The switch must be facilitated with an enclosed case so no one can turn it off by mistake.
m	The UPS wires will move from the ground floor UPS room to all the computers on the ground, first, and second floors.
n	Detailed notes will be provided in the drawings.
4.	The measurement may vary as per site measurement, so please do the marking and get it approved by the designer.
5	In case of any conflict final design will be as per consultation with the interior designer.
6	The design may alter as per the site condition.
7	The false ceiling will be at 9'150 mm, and the pop ceiling height is ~10' from the finished floor surface (may vary as per the site condition).
8	Drawing must be print on A3-sized paper.
9	All legends have a common meaning.
10	Furniture Notes:
a	All dimensions are in millimetre if units are missing.
b	Measurement may vary as per site measurement, so please do marking and get it approved by the designer.
	In case of any conflict final design will be as per consultation with the interior designer.

d	The design may alter as per the site condition.
e	The Inside laminate will be egg white laminate..
f	Please follow the 3D images for more details.
g	Electricity supply to the officer tables: 4 sockets and one 16Amp switch. The power supply to these sockets will be through UPS (under the table). The main power supply through socket with switch. Total 4+2 sockets and 1+1 switches. Provide a wire manger.
h	For door 4, 150 mm hinges. 1st hinge 150 mm from top, 2nd hinge 100 mm from 1st hinge, 3rd hinge will be at centre, and 4th hinge will be 150 mm from bottom.
i	Wardrobe hinges, 4 100 mm, will be as per the below arrangement: 1st hinge 150 mm from top, 2nd hinge 100 mm from 1st hinge, 3rd hinge will be at centre, and 4th hinge will be 150 mm from bottom.
j	Door lock, double turn lock, Vijayan 3.125 mm deadbolt or equivalent and made up of brass.
k	Wardrobe and table locks, double turn lock, Vijayan 3.5".
l	Regarding the partition wall, it has been mentioned in the material description.
m	A wooden (teak wood) strip around the plywood in furniture as per required and described in detailed drawing.
n	Electricity supply to the staff tables: 3 sockets and one 16Amp switch. The power supply to these sockets will be through UPS (under the table). The main power supply through socket with switch. Total 3+2 sockets and 1+1 switches.
11	additional and full detail of the project along with layout and detail drawing must be collected from the bank .



घोषणा

मैं/हम घोषणा करते हैं कि मैं/हम अनुबंध की उपरोक्त शर्तों से सहमत हैं और निविदा प्रस्तुत करने/आपूर्ति के निष्पादन के लिए सहमत हैं एवं शर्तों का पालना करने के लिए मैं पूर्ण सहमत हूँ।

निविदादाता फर्म के हस्ताक्षर मय सील

दिनांक :

पत्र व्यवहार का पत्ता
टेलीफोन/मोबाईल नं.